BRUHAT BANGALORE MAHANAGARA PALIKE

Name of work: Improvements to roads and drains at Jayamuni Layout and Venkatala Surrounding areas in ward no.01 at Yelahanka Sub Division

Agency:- Sri. RAMESH Y B

SCHEDULE-B

Sl No	App Qty	Description of work	Approved Rates of Sri. RAMESH Y B		
			Unit	Rate in Figures	Rate in Words
1	236.52	Removing & Refixing stone Slab of drain and pointing in Cm (1:3)	Sqm	88.70	Rupees Eighty Eight And Paise Seventy Only
2	640.23	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications.	Cum	205.84	Rupees Two Hundred Five And Paise Eighty Four Only
3	378.50	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5681.10	Rupees Five Thousand Six Hundred Eighty One And Paise Ten Only
4	11.05	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications and as per directions of the Engineer-in-charge.	MT	70744.85	Rupees Seventy Thousand Seven Hundred Forty Four And Paise Eighty Five Only
5	184.12	Providing laying plain/ reinforced cement concrete M20 Grade for Box Drain walls of thickness 10cm to 20cm including centering shuttering for work etc. complete as per approved drawing and design	Cum	12148.97	Rupees Twelve Thousand One Hundred Forty Eight And Paise Ninety Seven Only
6	491.58	Providing and laying pre-cast drain cover slab of 100mm thickness in CM1:3 including cost of all materials,labour,curing, transportation, loading, unloading etc.,as per doiirections of the Enineer-in-charge.	Sqm	2312.52	Rupees Two Thousand Three Hundred Twelve And Paise Fifty Two Only
7	34.80	Providing and laying Pre Cast Drain Cover slabs of 250mm thickness including cost of all materials, labour, curing, transportation,loading, unloading etc.,complete as per the direction of Engineer - In- Charge.	Sqm	5628.20	Rupees Five Thousand Six Hundred Twenty Eight And Paise Twenty Only
8	1127.12	Earth work in soil with hydraulic excavator of 0.9 cu.m. bucket capacity including cutting and loading in tippers, trimming bottom and side slopes. In accordance with requirements of lines, grades and cross sections, and transporting to the embankment location and complete as per specifications.	Cum	163.81	Rupees One Hundred Sixty Three And Paise Eighty One Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

18/2/19

S No	App Qty	Description of work	Approved Rates of Sri. RAMESH Y E		
			Unit	Rate in Figures	Rate in Words
9	2817.80	Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications.	Sqm	5.84	Rupees Five And Paise Eighty Four Only
10	422.67	Construction of granular sub-base of Grading II Material by providing close graded material, mixing in a mechaical mix plant at OMC, carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications. A. Plant Mix Method	Cum	1833.78	Rupees One Thousand Eight Hundred Thirty Three And Paise Seventy Eight Onl
11	422.67	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete	Cum	6862.40	Rupees Six Thousand Eight Hundred Sixty Two And Paise Forty On
12	2817.80	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift.	Sqm	105.00	Rupees One Hundred Five Only
13	564.80	Providing groove cutting for width of 5mm to 100m depth 80mm-100 including cost of cutting machine, generatoe & HOM of machinery, including cost of blade, coolant etc., including cleaning of groove & providing sand and hot birumen fillars, and filler metal etc., including cost of conveyance of all materials,. Labour, lead and lift charges and all other incidental charges as per drawing and as per specifications.	Rmt	134.45	Rupees One Hundred Thirty Four And Paise Forty Five Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone